CHITALDRUG DIVISION.

Notification dated 8th August 1930.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 25th August 1930, for restoring Hirekandavadi minor Tank, Registered No. 35 of Holalkere Taluk and its main feeder.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1931.

2. The plans, detailed estimate and [illegible] can be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 [illegible] on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred and fifty (250) in cash or Government Promissory Notes, and must be superscribed "Tender for restoring Hirekandavadi minor tank Reg. No. 35 of Holalkere Taluk" and its main feeder, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquires regarding the acceptance or rejection of any tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate showing the quantities for restoring Hirekandavadi Minor Tank Reg. No. 35 of Holalkere Taluk and its Main feeder.

No.	Details	Per	Quantity
	Bund R. L. 55·00.		
1	Jungle clearing on the slopes of the bund and forming [illegible] on the slope.	L. S.	...
2	Earthwork to bund including watering and consolidation	C.yd.	5,900
3	Turfing the slopes of the bund ...	S.yd.	6,175
4	New stone revetment ...	C.yd.	342
5	Grade stones for new length of bund with figures cut and painted.	Each	6
6	Removing and refixing the existing grade stones including figuring with chisling and painting.		19
7	Gauge stones ...	,,	1
8	Construction detail stone ...	,,	1
9	Top width stones ...	,,	25
	SLUICES.		
	Providing a new plug with iron rod and locking arrangements etc., complete.	L. S.	...
	Waste Weir R. L. 56·00.		
1	Earthwork excavation ...	C.yd.	58
2	Burnt brick in surki mortar ...	C.ft.	204
3	Burnt stone slabs 6" thick... ...	S.ft.	112
4	Plastering with surki mortar ...	Sq.	1·09
	RESTORATION OF FEEDER CHANNELS.		
	No. 1. Feeder Channel		
1	Earthwork excavation and forming bank ...	C.yd.	1,821
	No. 2 Feeder Channel		
1	Earthwork excavation and forming bank		
	Hard soil ...	C.yd.	4,425
	Soft soil ...	,,	2,705
	Burnt stone revetment ...	L. S.	...
	Jungle clearing ...	S.yd.	9,720
	No. 3 Feeder Channel.		
	Earthwork excavation and forming banks.		
	Ordinary soil	C.yd.	2,111
	Jungle clearing thickly grown up ...	S.yd.	7,960